

GEORGE BUSH AIRPORT CHILLED/HOT WATER LOOP



OWNER:	Houston Airport System
GENERAL CONTRACTOR:	Construction LTD
ENGINEER:	IA Naman & Associates
BOYER CONTRACT:	\$3,100,000
TYPE OF CONTRACT:	Subcontractor
PROJECT TYPE:	New Chilled/Hot Water Loop
COMPLETION DATE:	September 2000

Boyer, Inc. was required to work in close proximity to major roads, taxiways, and aircraft operation areas while not disrupting any traffic or aircraft operations. We installed 1760 feet of 48" diameter steel casing using the Jacked Pipe Tunnel method under roadways and taxiways and 5780 feet of 30" preinsulated welded steel pipe to ASME B31.1, 100% X-Ray, in open cut next to roadways, taxiways, and aircraft operation areas. The project will finish on schedule with no disruption to traffic and aircraft operations. The project began in March 2000 and completed in September 2000.

